



PATIO DOOR INSTALLATION

—UNITS MUST BE INSTALLED:

- A. PLUMB
- B. LEVELED
- C. SQUARE
- D. SHIM

NOTE: CONSULT LOCAL BUILDING CODES
PRIOR TO INSTALLATION.

